



## SportsPlay Equipment, Inc.

5642 Natural Bridge St. Louis, MO 63120 (314) 389-4140 (800) 727-8180 Fax (314) 389-9034  
www.sportsplayinc.com

### **SportsPlay 301-146 10' Merry-Go-Round Specifications**

#### Specifications:

- ❑ Consists of 6 plastisol coated deck sections manufactured from 12 ga. steel.
- ❑ Post is 2.5" solid steel post 48" long with rebar reinforcing, set with a 36" wide x 36" deep hole. Will take approximately 1280 lbs of concrete (16- 80 lb bags). Concrete must cure 7 days before installation of merry go round.
- ❑ Mechanical governor to limit speed
- ❑ 1.5" solid steel ball bearing
- ❑ Bolt together assembly, which allows for easy replacement of any damaged parts.
- ❑ 6 Handrails are manufactured with 1 5/8" O.D. pipe welded together for easy installation.